# TTAG AHU-1 Replacement

22M.40

47.10 **Priority Score:** 

**Project Type:** Replacement **Priority Level:** Moderate

**Growth Related?:** No **Department: Corporate Services** 

Staff Contact: Kristan Shrider Estimated Useful Life (years): 25

| Cash Flow Projection:     | 2022       | 2023       | 2024+ |
|---------------------------|------------|------------|-------|
| Studies                   |            |            |       |
| In House Engineering      |            |            |       |
| Design or Engineering     | \$ 10,000  |            |       |
| Communication / Signage   |            |            |       |
| Construction / Contractor | \$ 100,000 | \$ 115,000 |       |
| Materials                 |            |            |       |
| Equipment/Misc            |            |            |       |
| Contingency               |            |            |       |
| Total                     | \$ 110,000 | \$ 115,000 | \$0   |
|                           |            |            | 1     |

#### **Description and Rationale:**

The TTAG is served by four indoor air handling units (AHU), with remote roof mounted condensing units. AHU-1 is a 15 ton unit that was installed in 2004 and serves the main gallery area. The AHU takes the outdoor air, reconditions it and supplies it as fresh air to the building. The condensing unit of AHU-1 failed (refrigerant leak) and a temporary unit has been installed until the replacement is in place. The current refrigerant in the system is R22 and will be replaced with R407 or R410 refrigerant (both have less environmental impact). Staff will explore opportunities for rebate programs.

#### Costs Incurred to 2021 Year End

**Impact on Operating Budget** \$0 \$0

**Total Project Budget:** \$ 225,000

### Schedule:

Construction Start Date: 05/01/2022

Substantial Completion or

purchase date: 03/30/2025

# **Funding Sources:**

| Tax Levy        | \$ 225,000 |
|-----------------|------------|
| Please Select   | \$ 0       |
| Capital Reserve | \$ 0       |
|                 |            |



# TTAG AHU-1 Replacement

22M.40

Priority Score: 47.10

#### **Justification for Matrix Values**

# **Score 0 - 5**

# **Justification / Rationale for Rating**

| People                  | How many people will be directly impacted by the project?  | 5 | > 10,000.   |
|-------------------------|--|---|---|
| Health and Safety       | What is the risk to the health and safety of the public or Staff if the project does not proceed?  | 1 | Proper air quality is critical in buildings. If air quality is not adequate, health issues can occur. |
| Legislation             | Is the project required for legislative/regulatory compliance?   | 3 | Project will move organization closer to meeting the asset mgmt. plan.                                |
| Asset Management        | Is the project a high priority for replacement in the asset management plan.   | 5 | High probability of failure; high consequence.  |
| Operational Performance | If the project proceeds (or fails to proceed), what will be the impact on operational performance? Comment on any impact on operating costs, staff time and maintenance. | 2 | Slight impact on operational efficiency and effectiveness.  |
| Financing               | Can the cost of investment be leveraged or are there partnership funds available?  | 1 | May be eligible for rebate.   |
| Environment             | Does the project address needs impacted by climate change?   | 2 | Slightly improve the natural environment or prevent further detriment.                                |
| Socio-Economic Factors  | To what degree does the project support diversity and inclusion Initiatives?   | 2 | Maintains an existing public space.   |
| Strategic Plan          | Does the project help to meet a Key Result in the Strategic Plan?  | 1 | Core service delivery. Providing safe facilities and spaces for activities.                           |
| Public Input            | Has the project been identified through public engagement?   | 1 | Has been mentioned in unsolicited feedback.   |